



## PARTIAL ENLARGED PLAN - PROPOSED IMPROVEMENTS

# LIMIT OF WORK 2"x2"x3'-0" WOODEN STAKE OR I/2" STEEL POST. SEE NOTES ON THIS SHEET. 3" MIN. 4" MAX. COMPOST FILTER SOCK FILLED WITH COARSE COMPOST SEE PLAN FOR SIZE TURN LIP UPWARDS AT ENDS EXCESS SOCK MATERIAL DRAWN AND TIED OFF AT STAKE. (TYP.) \*2'-0" AT 30° ANGLE EACH END TO PREVENT FLOW AROUND (TYP.) 2"x2"x3'-0" WOODEN STAKE SPACED EVERY 3'-0" O.C. (TYP.)

#### COMPOST FILTER SOCK GENERAL NOTES

- FILTER SOCKS CAN BE PLACED AT THE TOP, ON THE FACE, AND AT THE TOE OF SLOPES AS SEDIMENT-TRAFPING DEVICES FOR SHEET FLOW RUNOFF AND SEDIMENT PER THESE NOTES AND COMPOST FILTER SOCK DETAILS, PLANS, AND SPECIFICATIONS.
- INSPECT FILTER SOCKS AFTER EACH RUNOFF EVENT. REMOVE AND REPLACE IF SIGNS OF UNDERCUTTING OR DOWNSTREAM RILLS ARE OBSERVED.



# GENERAL NOTES

- THE CONTRACTOR SHALL PROVIDE A MINIMUM 12 HOURS ADVANCE NOTICE TO THE TOWN PRIOR TO PROJECT MOBILIZATION.
- 2. THE CONTRACTOR SHALL STRICTLY ADHERE TO THE CRMC MAINTENANCE ASSENT ISSUED SPECIFIC TO THE PROJECT.
- 4. THE CONTRACTOR SHALL VISIT THE SITE TO VERIET, AND BE FILLY AWARE OF, EXISTING CONDITIONS PRIOR TO THE START OF WORK AND SHALL IDENTIFY ANY EXISTING ITEMS OF WORK SCHEDULED TO REPURING TO SEE SALVAGED FOR RE-USE IN COORDINATION WHIT THE TOWN AND AS INDICATED IN THESE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL MEET WHIT TOWN REPRESENTATIVES TO DISCUSS THE PROJECT AND CRIVE PERMIT REQUIREMENTS PRIOR TO THE START OF CONSTRUCTION.
- Underground utilities have not been marked in the field, and records have not been obtained specific to this project. Therefore, the contractor must obtain and verify the locations of all estimans utilities, overhelds and inderground, and properly notify 'Dig-Sape's price to compension any construction operations, all utility 'Organisation and minicipal departments' haves facilities may be affected by any more to be prepared by the contractor shall be notified at least 12 hours in advance
- ALL SITE WORK AND MATERIALS SHALL CONFORM TO THE STATE OF RHODE ISLAND STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION, AND THE REGULATIONS AND STANDARDS OF THE TOWN OF BRISTOL, AS APPLICABLE.
- 8. SLOPE STABILIZATION MAT SHALL BE GEOMED® 3D VEGETATED SLOPE PROTECTION, 64 DEEP, AS MANIFACTURED BY PRESTO GEOSYSTEMS® (OR EQUAL), 610 N PERKINS STREET, PO BOX 2349, APPLETON, MISCONSIN 54912; TOLL-FREE PHONE. (620) 546-3424, PHONE. (420) 136-1329; FAX. (420) 136-1222; BYAILL. NECOPPRESTOCEOCOM. GEOMED SLOPE PROTECTION SHALL BE INSTABLED IN STRUCT ADMERISME TO MANIFACTURERS SPECIFICATIONS WITH ALL PROPER INSTABLED.

- 9. ANY ITEMS OF WORK NOT SPECIFICALLY INDICATED ON THE PLANS BUT REQUIRED FOR COMPLETE CONSTRUCTION OF THE PROJECT WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND SHALL BE INCLIDED IN THE CONTRACT PRICE. IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL EXISTING SITE CONDITIONS.
- THE CONTRACTOR SHALL LANFILLY DISPOSE OF ALL MATERIALS REMOVED THAT ARE NOT SCHEDULED FOR SALVAGE OR REUSE. THE TOWN SHALL BE THE SOLE JUDGE OF ANY ITEMS THAT MAY BE SUITABLE FOR SALVAGE AND REDGE IN THE MORK.

# PLANTING AND SEEDING NOTES

- GEOMED® SLOPE STABILIZATION MAT SHALL BE PLANTED WITH A SALT TOLERANT GRASS-SEED MIX COMPOSED SOLELY OF SLENDER AND STRONG CREEPING RED FESCUES (FESTUCA RUBRA L. VAR.), PLANTED AT A RATE OF 4 TO 5 POUNDS PER I,OOO SQUARE FEET, OR AS OTHERWISE APPROVED BY THE TOWN.
- 3. AREAS OF EVISTINS LAWN THAT NAY NEED TO BE LOAMED AND SEEDED OUTSIDE THE LIMITS OF CHEB INSTALLATION AS A RESULT OF PROJECT ACTIVITIES OR DAYAGE SHALL RECEIVE AT LEAST 4 INCHES OF PLANTABLE LOAM (IF NOT CURRENILTY PRESENT) AND SHALL BE SEEDED WITH A HIGH-QUALITY, PILL-SUN GRASS MIX (CONTAINING AT LEAST 50 PERCENT KENTUCKY BLUEGRASS) TO MATCH EXISTINGTURE.

### GOOD HOUSEKEEPING NOTES

- ALTHOUGH LIMITED PERIMETER EROSION AND SEDIMENTATION CONTROLS HAVE BEEN IDENTIFIED FOR THE PROJECT, THE TOWN RESERVES THE RIGHT, AT NO ADDITIONAL COST TO THE TOWN, TO SPECIFY SUCH CONTROLS THE NEED, RISES, THE CONTRACTOR IS RESPONSIBLE FOR GOOD HOUSEKEEPING PRACTICES AND APPROPRIATE EROSION AND SEDIMENTATION CONTROL METHER SPECIFICALLY ADDRESSED IN THE CONTRACT DOCUMENTS OR NOT.

- DISTURBED LAWN OR PLANTING BEDS THAT REMAIN EXPOSED AS OF OCTOBER IS SHALL BE SEEDED OR OTHERWISE STABILIZED AS OF THAT DATE. ANY AREAS THAT DO NOT EXHIBIT ADEQUATE VEGETATION STABILIZATION BY NOVEMBER IS MUST BE STABILIZED BY INSTALLING EROSION-CONTROL MATTING OR EQUIVALENT, AS AFPROVED BY THE TOWN.
- EARTHEN-MATERIALS STOCKPILES TO REMAIN IDLE MORE THAN 14 DAYS ARE TO BE RINGED WITH PROPERLY STAKED COMPOST FILTER SOCK, OR EQUIVALENT.
- 5. APPROPRIATE PRECAUTIONS SHALL BE TAKEN TO PREVENT CONSTRUCTION EQUIPMENT FROM TRACKING SOIL BEYOND PROJECT LIMITS ONTO PAVED SURFACES AND PUBLIC STREETS.
- 6. THE CONTRACTOR SHALL LIMIT OPERATIONS THAT RESULT IN THE GENERATION OF AIRBORNE SEDIMENT AND SHALL BE RESPONSIBLE FOR DUST CONTROL. SUCH CONTROL. SHALL INCLUDE, AS APPLICABLE, SMEEPING OF ANY OFF-SITE LOCATIONS THAT MAY BECOME IMPACTED BY SITE CONSTRUCTION.

PARTIAL ENLARGED PLAN - PROPOSED **IMPROVEMENTS** 





